

Di Giorgio ERATE

Addendum #3

2/5/2015

Response to Vendor Questions:

1. For the structured cabling portion, I don't show reference on whether CAT 6 Patch Cords and fiber patch cords are required in this bid?

a. IF yes, what lengths and quantity?

The Hardware and Structured Cabling is being bid separately. The Cabling portion is responsible for to the Cat6 patch panels in all network boxes and server connection location. The winning bidder on Hardware will be responsible for PROVIDING and INSTALLING appropriate length Cat6 and Fiber Patch Cables and routing them within the provided Cable Management in all Network Boxes and Locations.

The district is requiring 50 of each 6, 10, 15 foot patch cables to be provided by the STRUCTURED CABLING BIDDER.

2. For the network server portion, is the requirement that the vendor provide the servers installed with software and licenses and the District will migrate their applications to these new servers OR is the requirement that the vendor is to perform the migrations?

a. If the vendor is to perform the migrations, can you detail each application that needs to be migrated?

4. Network Server

The district is requesting bids for two (2) 3U rack mounted servers. The servers shall include multiple

processors, high availability drives and NIC's, and MS Windows Server Operating System on both units and

Windows Exchange software one (1) unit. The servers are designed to provide DNS, DHCP, and print sharing

services for the entire district. Installation and configuration shall be included in the submitted bids.

A Standard Server Install is being asked for with the current Exchange set up to be migrated over.

3. Tim had mentioned you'd be sending maps of cable drops locations, can you give us an ETA on when these will be sent?

In place of a drawn map, please refer below:

Addendum #2 January 13, 2015

The description is adequate to describe the correct location of the drops. Examples pulled from the Addendum:

**R8-10 Wing R8-10 has Janitor and Snack Bar Room
2 W wall Snack Bar, 2 under IDF in Janitor Room
1 ceiling in each room near E wall
3 N, 3 W, east Wall 2 north, 3 south in each room
R11 1 ceiling near S wall
10 N , 5 W, 2S (west corner)
R12 No Ceiling drop**

**Library 1 ceiling drop near E wall
12 W, 3E**

Subflooring dual box for 4 data drops each and 2 power at Librarians desk

3 Subflooring dual boxes for 4 data and 2 power arranged West-East in middle of floor

Stage 3 drops near existing desk

2 drops on stage replacing existing recess with dual box allowing for microphone connection in same recess